



Stanley H. Kellerhouse Municipal Building
One Van Wyck Street
Croton-on-Hudson, NY 10520-2501

Mayor
Leo A. W. Wiegman
Trustees
Ann H. Gallelli
Maria Slippen
Kevin W. Davis
Andrew Levitt
Manager
Abraham J. Zambrano

Clerk
Pauline DiSanto
Engineer
Daniel F. O'Connor, P.E.

June, 2014

**WATER MAIN REPLACEMENT, CEMENT LINING AND EXTENSION
PROJECT: HARMON AREA, WOLF ROAD/COOK LANE AREA, AND
MUNSON AND LOCONTO STREETS (2014-2015)**

Dear Resident:


In anticipation of the work on the water distribution system improvements scheduled to begin in July, the Village of Croton-on-Hudson invites you to attend a community meeting about the project on **Thursday, June 26, 2014, 8:00 p.m.** at the Harmon Firehouse, 30 Wayne Street.


Village trustees, Village staff, and the contractor for the project, Heitkamp, Inc., will present detailed information about the water distribution system improvement project, including timeframes, phasing, benefits, cost, and more information about the improvements. There will be a question and answer session after the presentation.


For more information on the project, please see the attached project summary and location map.


If you have any questions about the meeting, please contact the Engineering Department at 271-4783 or engineering@crotononhudson-ny.gov.

We look forward to your participation.


Daniel O'Connor, P.E.
Village Engineer


John Spatta
Water Foreman


Jan Wines
Water Systems Specialist


Ronnie Rose
Administrative Coordinator

Water Main Replacement, Cement Lining and Extension
Project: Harmon Area, Wolf Road/Cook Lane Area,
and Munson and Loconto Streets
(2014-2015)

Project Summary: Existing unlined cast iron water mains will be scraped out and cement lined, new water mains will be installed to increase fire flows and provide mains on streets that currently have no water main. New valves will be installed to enhance system operation and maintenance and new fire hydrants installed to enhance fire fighting operations.

Contractor: Heitkamp, Inc, Watertown, CT, contract awarded May 9, 2014

Project Areas (see map for locations):

Wolf Road and Cook Lane Area

Harmon Area

Munson Street and Loconto Street

Details:

- 7,370 feet of new cement lined ductile iron pipe water main being installed
 - 750 feet of new 10" mains
 - 4500 feet of new 8" mains
 - 2000 feet of new 6" mains and 120 feet of new 4" main
- 24,100 feet of existing unlined cast iron water main being cement lined
- 45 new or replacement fire hydrants being installed
- 133 new or replacement valves being installed

Phasing: Improvement work to be done in five phases

Time Frames: Construction to start July 2014 and ends July 2016

Benefits: Improvement in water quality (elimination of brown water, reduction in chlorine demand, improvement in taste), improvement in flow and fire protection capability, and improvement in system operations.

Cost: \$5,441,612.70